

**RFP ADDENDUM NO. 1**  
 Date of Addendum: October 7, 2020

<b>NOTICE TO ALL POTENTIAL RESPONDENTS</b>
The Request for Proposals (RFP) is modified as set forth in this Addendum. The original RFP Documents and any previously issued addenda remain in full force and effect, except as modified by this Addendum, which is hereby made part of the RFP. Respondent shall take this Addendum into consideration when preparing and submitting its Proposal.

<b>2. Scope of Work.</b>
--------------------------

Description of Change
-----------------------

Paragraph Two under **Scope of Work** will be edited to read as follows: "Proposal shall include the cabling and installation for three (3) new **light** fixtures. Fixtures ~~will be like adjacent fixtures~~ **may be can/downlights or flat panel LED lights as best suits the placement** or as directed by Owner."

Paragraph Six under **Scope of Work** will be edited to read as follows: "It is the contractors responsibility of verify the number of fixtures, the type LED replacement lamp for each fixture and make certain that their proposal accounts for all fixtures and replacement lamps including emergency type fixtures. **Contractor is responsible for all construction for installing additional light fixtures.**"

Add Paragraph Seven as follows: "**There are existing string lights installed around the curved ceiling at the Circulation Desk and down both sides of the length of the Main Entry Hall. Contractor will provide suitable replacement lights in both places to better illuminate the Circulation Desk and the Main Entry Hall. The length of such lighting should be determined by the Contractor during the onsite inspection.**"

Section **Work will also include** will be edited to read as follows:

- Remove and properly recycle fluorescent lamps.
- Remove and properly recycle all ballasts.
- Installing emergency backup batteries for emergency fixtures are where applicable.
- Replace all active end connectors (tombstones).
- Adding electrical cabling and three (3) light fixtures as directed by Owner. See below.
- Installation of ~~over counter~~ **more suitable lighting** around circulation desk **and down both sides of main entry hall.**

Section **New fixtures to be located** will be edited as follows:

Circulation Desk	<del>Troffer In Ceiling</del>	East side of circulation desk. Add a fourth (4th) <b>light</b> fixture in line with existing
------------------	-------------------------------	---

		fixtures. <del>Fixture to be like other fixtures.</del> <b>Fixture can be can downlight or as best suits the placement.</b>
Non-Fiction Stacks	<del>Flat Acrylic in Drop Ceiling</del>	Northwest corner of building along west wall. Add two (2) fixtures in line with existing fixtures. <del>Fixtures to be like other fixtures.</del> <b>Fixture can be can downlight, flat panel LED or as best suits the placement.</b>

**Section Location and Replacement Lamps** will be edited as follows:

Outside Entry	Hanging Exterior	<del>9 Watt A19 Non-Dimmable 40K LED</del> 7 Watt PL Bulb 40K (G24Q) Frosted LED	1
Circulation Desk	<del>Over Counter Lights</del> <b>String Lights</b>	High density LED strip CE certified Low-heat rated at 50,000 hours <b>or as best suites the placement</b>	<del>1</del> <b>Contractor to determine</b>
Main Entry Hall	<b>String Lights</b>	High density LED strip CE certified Low-heat rated at 50,000 hours <b>or as best suites the placement</b>	<b>Contractor to determine</b>

END OF ADDENDUM